

Florida Department of Transportation
Bid Solicitation Notice and Approximate Quantities

Letting: CT170614 Call Order: 016 Proposal: T5588 District:05
 Counties: DIST/ST-WIDE, FLAGLER, VOLUSIA
 Road Name: SR 9 (I-95)
 Limits: AT THE INTERCHANGES WITH LPGA BLVD, SR 5 (US 1), OLD DIXIE HWY, SR 100 AND PALM COAST PKWY
 Project(s): 43505915201(*) Federal Aid No: 0954141I
 Total Roadway Length: 21.176 Miles Contract Days: 590
 Total Bridge Length: 0.000 Miles Letting Date: 06/14/17
 Total Proposal Length: 21.176 Miles Contract Execution Days: 10
 Special Start Date: N/A
 Aquis/Flexible Start Time: 120 Calendar Days

Proposal Budget Estimate: \$7,284,680.00

Please read the full advertisement

Description:

The improvements under this contract consist of the installation of highway signing and lighting on SR 9 (I-95).

Call Order: 016 Proposal: T5588

ALT	Item	Description	Unit	Quantity
Section 0001 Roadway				
	0101- 1-	MOBILIZATION (43505915201)	LS	1.000
	0102- 1-	MAINTENANCE OF TRAFFIC (43505915201)	LS	1.000
	0102- 14-	TRAFFIC CONTROL OFFICER	HR	120.000
	0102- 60-	WORK ZONE SIGN	ED	17,700.000
	0102- 74- 1	CHANNELIZING DEVICE- TYPES I, II, DI, VP, DRUM, OR LCD	ED	318,600.000
	0102- 76-	ARROW BOARD / ADVANCE WARNING ARROW PANEL	ED	240.000
	0102- 99-	PORTABLE CHANGEABLE MESSAGE SIGN, TEMPORARY	ED	250.000
	0102-150- 1	PORTABLE REGULATORY, SIGN	ED	220.000
	0102-150- 2	RADAR SPEED DISPLAY UNIT	ED	220.000
	0104- 10- 3	SEDIMENT BARRIER	LF	13,675.000
	0999- 25-	INITIAL CONTINGENCY AMOUNT, DO NOT BID (43505915201)	LS	1.000
Section 0002 Signing				
	0700- 3-203	SIGN PANEL, FURNISH & INSTALL OVERHEAD MOUNT, 21-30 SF	EA	22.000
	0700- 3-205	SIGN PANEL, FURNISH & INSTALL OVERHEAD MOUNT, 51-100 SF	EA	6.000
	0700- 3-206	SIGN PANEL, FURNISH & INSTALL OVERHEAD MOUNT, 101-200 SF	EA	7.000
	0700- 3-207	SIGN PANEL, FURNISH & INSTALL OVERHEAD MOUNT, 201-300 SF	EA	9.000
	0700- 3-603	SIGN PANEL, REMOVE, 21-30 SF	EA	19.000
	0700- 3-604	SIGN PANEL, REMOVE, 31-50 SF	EA	3.000
	0700- 3-625	SIGN PANEL, REMOVE, 51-100 SF WITH LIGHTING	EA	2.000
	0700- 3-626	SIGN PANEL, REMOVE, 101-200 SF WITH LIGHTING	EA	11.000
	0700- 3-627	SIGN PANEL, REMOVE PANEL, 201-300 SF WITH LIGHTING	EA	9.000
Section 0003 Lighting				
	0630- 2- 11	CONDUIT, FURNISH & INSTALL, OPEN TRENCH	LF	78,156.000
	0630- 2- 12	CONDUIT, FURNISH & INSTALL, DIRECTIONAL BORE	LF	28,835.000
	0630- 2- 15	CONDUIT, FURNISH & INSTALL, BRIDGE MOUNT	LF	2,415.000
	0635- 2- 11	PULL & SPLICE BOX, F&I, 13" x 24" COVER SIZE	EA	626.000

Call Order: 016 Proposal: T5588

ALT	Item	Description	Unit	Quantity
	0635- 3- 11	JUNCTION BOX, FURNISH & INSTALL, AERIAL	EA	62.000
	0639- 1-111	ELECTRICAL POWER SERVICE, F&I, OVERHEAD, METER FURNISHED BY POWER COMPANY	AS	7.000
	0639- 1-121	ELECTRICAL POWER SERVICE, F&I, UNDERGROUND, METER FURNISHED BY POWER COMPANY	AS	2.000
	0639- 6- 1	ELECTRICAL POWER SERVICE- TRANSFORMER FURNISH & INSTALL	EA	2.000
	0641- 2- 12	PRESTRESSED CONCRETE POLE, F&I, TYPE P-II SERVICE POLE	EA	9.000
	0715- 1- 11	LIGHTING CONDUCTORS, F&I, INSULATED, NO. 10 OR <	LF	9,145.000
	0715- 1- 12	LIGHTING CONDUCTORS, F&I, INSULATED, NO.8 - 6	LF	249,368.000
	0715- 1- 13	LIGHTING CONDUCTORS, F&I, INSULATED, NO 4 TO NO 2	LF	110,787.000
	0715- 1- 15	LIGHTING CONDUCTORS, F&I, NO.1/0 - 3/0 (0 to 000)	LF	7,613.000
	0715- 1- 60	LIGHTING CONDUCTORS, REMOVE & DISPOSE, CONTRACTOR OWNS	LF	58,480.000
	0715- 4-122	LIGHT POLE COMPLETE, F&I, WIND SPEED 130, POLE HEIGHT 45'	EA	472.000
	0715- 7- 11	LOAD CENTER, F&I, SECONDARY VOLTAGE	EA	9.000
	0715- 7- 41	LOAD CENTER, REMOVE, SECONDARY VOLTAGE	EA	7.000
	0715- 11- 9	LUMINAIRE, UNDER DECK PENDANT, F&I PROJECT 435059-1-52-01	EA	5.000
	0715- 11-125	LUMINAIRE, F&I, UNDER DECK, WALL MOUNT	EA	28.000
	0715- 11-500	LUMINAIRE, REMOVE	EA	12.000
	0715- 19-122	HIGH MAST LIGHT POLE, F&I, WIND SPEED-130 MPH, POLE 100'	EA	4.000
	0715-500- 1	POLE CABLE DISTRIBUTION SYSTEM, CONVENTIONAL	EA	501.000
	0715-500- 2	POLE CABLE DISTRIBUTION SYSTEM, FURNISH & INSTALL, HIGH MAST	EA	4.000
	0715-512-145	LIGHT POLE COMPLETE- SPECIAL DESIGN, F&I, DOUBLE ARM SHOULDER MOUNT, ALUMINUM, 45'	EA	9.000
	0715-512-150	LIGHT POLE COMPLETE- SPECIAL DESIGN, F&I, DOUBLE ARM SHOULDER MOUNT, ALUMINUM, 50'	EA	8.000
	0715-512-155	LIGHT POLE COMPLETE- SPECIAL DESIGN, F&I, DOUBLE ARM SHOULDER MOUNT, ALUMINUM, 55'	EA	8.000
	0715-512-160	LIGHT POLE COMPLETE- SPECIAL DESIGN, F&I, DOUBLE ARM SHOULDER MOUNT, ALUMINUM, 60'	EA	4.000